Manafa Tech | Assignment

Tasks:

- Using Terraform, and Oracle Cloud Infrastructure (OCI), build a hop-and-spoke network and all of its necessary components
- Provision an application VM with Nuxt.js as a frontend and Laravel as a backend
- Provision a database VM with MySQL, Redis and Mongo
- Setup an automated CI/CD deployment using Jenkins
- Use Ansible to install and configure all systems

Name: Muhammad Abdullah Email: mabdullah.my@gmail.com

Call: +923441801517

Hub and Spoke Network

I used a Terraform to deploy the hub and spoke infrastructure. The components configured through Terraform are given below:

- Three VCNs
- Internet Gateway for Hub VCN
- Local Peering Gateways
- Subnets
- Route Tables


The Terraform code is here:

https://github.com/magoldev/manafa-assignment/tree/main/hub-and-spoke

Note: Some components (WAF, Firewall etc) of the below diagram are not part of the Terraform code to meet the submission deadline.

Here is the draw.io link

https://drive.google.com/file/d/1vsEYfnQj3FU3HMfqEFwTIZG9d7n8OVfv/view?usp=sharing



Provisioning of VMs

VMs are also provisioned by Terraform

Separated VMs for Application and Database in spoke1 VCN.

Installation of prerequisites with Ansible

Using Ansible to configure application prerequisites.

Here is the link to Ansible playbooks and roles.

https://github.com/magoldev/manafa-assignment/tree/main/Ansible

Deployment of Application

Databases

- MYSQL using Ansible
- MONGO using Ansible
- Redis using Ansible

For Nuxt JS (Frontend)

- Ubuntu OS
- Install Node and PM2
- Clone code frontend branch (https://github.com/magoldev/laravel-nuxt-app)
- Install node dependencies (npm install)
- Build code (npm run build)
- Run with PM2

For Laravel (Backend)


- Install PHP FPM with Ansible
- Install Laravel Composer
- Clone code backend branch (https://github.com/magoldev/laravel-nuxt-app)
- Set env
- Install dependencies with the composer
- php artisan key:generate
- php artisan migrate
- Set permissions

Setup Nginx

- Use nginx as webserver
- Configure separate virtual hosts for Frontend and Backend
- Configurations of virtual hosts are available here


https://github.com/magoldev/manafa-assignment/tree/main/nginx-configurations

Application Flow



CI/CD with Jenkins

Flow of Jenkins pipeline.



Configured separate declarative Jenkins pipelines for Frontend and Backend.

Assumptions:

- Forked a sample code from GitHub https://github.com/magoldev/laravel-nuxt-app
- Branch frontend for Frontend
- Branch backend for Backend

Jenkins Pipeline Code is here

https://github.com/magoldev/manafa-assignment/tree/main/Jenkins